BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Development of park at Hegadenagara in Ward No.06 Byatarayanapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	165.08	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavted surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification	cum	166.42	Rupees One Hundred Sixty Six and Forty Two Paise Only
2	165.08	Lead for earthwork and disposal of debris shall be payable at carriage rates by mechanical means including loading and unloading for earthwork (upto 15 kms) complete with all lead & lift & as per the direction of the Engineer in charges.	cum	100.00	Rupees One Hundred Only
3	4.69	Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth including cost of all materials, labour HOM of machinery curing complete as per specification, specification No.	cum	5598.92	Rupees Five Thousand Five Hundred Ninety Eight and Ninety Two Paise Only
4	5.00	Providing and fixing Executive bench made out of Sadarahally grey stone with hand supporter with three line finishing with arch design, with 100 mm slab height 90xlength 150 width 45 cms	Nos	18200.00	Rupees Eighteen Thousand Two Hundred Only
5	3.13	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills including cost of all materials, labour HOM of machinery curing complete as per specification, specification No. KBS 4, 1, 4.2	cum	5767.46	Rupees Five Thousand Seven Hundred Sixty Seven and Forty Six Paise Only
6	31.25	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification	sqm	1150.10	Rupees One Thousand One Hundred Fifty and Ten Paise Only

S.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	111.11	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete	Nos	331.78	Rupees Three Hundred Thirty One and Seventy Eight Paise Only
8	1.00	Providing Children Play Standard Sea Saw 2 Seater Equipment : This equipment is made up of main beam 50mm MS pipe 'A' class of length 1.98 mtr. With two handles welded at the ends as a hand are made of 20mm 'A' class pipe. The main beam is pivoted to the bottom supports of 40mm MS pipes by bush bearing clamped by pivot joints which swivel over 28mm dia steel shaft, which gets installed in the ground by means of concrete, 2 Nos. seats are made of 250 mm x 200 mm x 18 SWG MS sheets with T hand rest at the front. Air pipes are of ISI grade. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2;4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as per the drawing and specification and direction of the Engineer in charge of the work	Nos	28000.00	Rupees Twenty Eight Thousand Only
9	1.00	Providing children play standard duck wheel equipment. This is a macro reveier made up of an 4 feet diameter platform with 1.5mm thick aluminium chequered plate supported well at the bottom. There is a 100mm dia MS pipe at the cenetre with two Nos of ball bearing, 2 Nos LDPE ducks and 1 No of plastic sheet flat seats, all supported to vertical pillars of size 25mm NB pipes. The 100 rings are in 25mm pipe and bottom circular ring are of 32 mm NB pipes. All pipes are of IS grade. All the pipes are painted with two coats of super set paint over a coat of protective zinc chromate yellow oxide including fixing the play equipment in CC 1:2:4 curing etc, complete with all lead, lift loading unloading and any incidental charges required for the successful completion of the work (All FRP items gel water finish or stoving paint in overns) as pe rthe Engineer in charge of the work	Nos	68000.00	Rupees Sixty Eight Thousand Only
10	1.00	2-Seater Swing : This Swing consists of 2 Nos, seat sof solid fibbed FP of size 480 mm x 180 mm x 3.5 mm supported by MS chains (*heavy) length 1.8 mtrs, each seat is suspended by 2 lines of chains. The chains are supported by circular housing with bearing from which the chain in suspended. The main beam is of 50mm MS 'a' class pipe. Size of MS chain 30mm x 20mm x 5mm thick, The 2 Nos inverted 'V' beams are of 50mm 'A' Class pipes secured at the top the main beam by means of CI castings. (Heavy duty for elders) All pipes are of ISI grade. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow oxide.	Nos	46000.00	Rupees Forty Six Thousand Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
13	2	Providing Children Play **Standard Slide Equipment**: Made out of M.S. 'A' class plpes:-Main frame are in 25mm and other railings are in 20mm, 1.5mtrs h x 3.00mtrs long x 0.45mtrs width, Sliding surface fitted with S.S. Sheet. All pipes are of ISI grade. All the pipes are painted with two coats of super set paint over a coat 0 protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other Incidental charges and as per the drawing and specification and direction of the Enalneer in charce of the work..	Nos	28000	Rupees Twenty Eight Thousand Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

Chief Engineer
Yelahanka Zone
Jnath Bangalore Mahanagara
Bangalore